





Solar Light Option



Side Panel Option



vario™ Express I with optional side panels shown in sandstone powder coat finish, with versatile™ 4C mailboxes (sold separately) shown in dark bronze powder coat finish

vario Express **

- Aluminum, corrosion resistant horizontal beams and die cast finials along with steel vertical uprights available in seven weather resistant powder coat finishes
- Powder coated aluminum mailbox casings, sized to match versatile[™] 4C mailboxes (sold separately), standard in each kit
- Pre-engineered mail station kit comes complete with all necessary hardware, including Hilti anchor system (see technical foundation plans for additional mounting details)
- Optional solar light kit available (see sentinelTM solar site lite technical documents for product details)
- Optional side panels include coated pressure preserved plywood interior & powder coated aluminum exterior

Color Options

Customize your vario™ Express mail station with ten different architectural powder coat finishes
*Note: sentinel™ solar site lite option only available in Sandstone, Black and Postal Grey powder coat finish

Dark Bronze PMS Black 7C

Sandstone PMS 75017C **Black** PMS Black 6C

Blonde Gold PMS 7536C Postal Grey PMS 413C

> White PMS White

Silver Speck PMS 877C

Forest Green PMS 3308C Antique Copper* PMS 876C

Antique Bronze* PMS 8622C

* NEW Colors

VARXP1

Installed Kit Height(with finials)	7'-71/8"	
Installed Kit Height(with lights)	12′-10 ^{1/2} ″	
Installed Kit Depth(w/o panels)	1′-6 ^{1/2} "	
Installed Kit Depth(with panels)	1'-7"	
Installed Kit Width(w/o panels)	4'-01/8"	
Installed Kit Width(with panels)	4′-5 ^{3/8} ′	
Maximum Mailboxes	20	
Minimum Parcel Lockers (1:10 ratio) 2		
4C Suite Compatibility A	,C,E,F,G, \vdash	



VARXP2

Installed Kit Height(with finials)	7'-71/8"	
Installed Kit Height(with lights)	12'-101/2"	
Installed Kit Depth(w/o panels)	1′-6 ^{1/2} ″	
Installed Kit Depth(with panels)	1'-7"	
Installed Kit Width(w/o panels)	5′-6 ^{7/8} ″	
Installed Kit Width(with panels)	6′-01/2″	
Maximum Mailboxes	29	
Minimum Parcel Lockers (1:10 ratio) 3		
4C Suite Compatibility A	,C,E,F,G,H	



VARXP3*

Installed Kit Height(with finials)	7'-71/8"	
Installed Kit Height(with lights)	12′-10 ^{1/2} ″	
Installed Kit Depth(w/o panels)	1'-6 ^{1/2} "	
Installed Kit Depth(with panels)	1'-7"	
Installed Kit Width(w/o panels)	8′-5 ^{3/4} ″	
Installed Kit Width(with panels)	8′-113/8″	
Maximum Mailboxes	49	
Minimum Parcel Lockers (1:10 ratio) 5		
4C Suite Compatibility A	,C,E,F,G,H	



VARXP4*

Installed Kit Height(with finials)	/'-/1/8"	
Installed Kit Height(with lights)	12′-10 ^{1/2} ″	
Installed Kit Depth(w/o panels)	1'-6 ^{1/2} "	
Installed Kit Depth(with panels)	1'-7"	
Installed Kit Width(w/o panels)	9′-6³/4″	
Installed Kit Width(with panels)	10′-01/2″	
Maximum Mailboxes	60	
Minimum Parcel Lockers (1:10 ratio) 6		
4C Suite Compatibility A	,C,E,F,G,H	



* Note: vario™ Express III and IV can be connected end-to-end to create a larger mail station, using optional mid-section kit



Find an Authorized Florence Dealer online at florencemailboxes.com/dealers